AN UPDATE ON THE HYCOM SOLAR RADIATION PENETRATION SCHEME

By

A. BIROL KARA

ALAN WALLCRAFT, HARLEY HURLBURT AND ZHONGPING LEE

Naval Research Laboratory (NRL)

Stennis Space Center

maintaining the data needed, and c including suggestions for reducing	ompleting and reviewing the collect this burden, to Washington Headqu uld be aware that notwithstanding ar	o average 1 hour per response, includion of information. Send comments a arters Services, Directorate for Informy other provision of law, no person a	regarding this burden estimate of mation Operations and Reports	or any other aspect of th , 1215 Jefferson Davis l	is collection of information, Highway, Suite 1204, Arlington	
1. REPORT DATE OCT 2004		2. REPORT TYPE		3. DATES COVE 00-00-2004	red I to 00-00-2004	
4. TITLE AND SUBTITLE				5a. CONTRACT NUMBER		
An Update on the l	HYCOM Solar Radi	cheme	5b. GRANT NUMBER			
			5c. PROGRAM ELEMENT NUMBER			
6. AUTHOR(S)			5d. PROJECT NUMBER			
					5e. TASK NUMBER	
					5f. WORK UNIT NUMBER	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Naval Research Laboratory, Stennis Space Center, MS, 39529				8. PERFORMING ORGANIZATION REPORT NUMBER		
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSOR/MONITOR'S ACRONYM(S)		
				11. SPONSOR/M NUMBER(S)	ONITOR'S REPORT	
12. DISTRIBUTION/AVAIL Approved for publ	LABILITY STATEMENT ic release; distributi	on unlimited				
13. SUPPLEMENTARY NO 8th HYCOM NOP		Oct. 27-29, 2004, R	SMAS, Miami, F	L		
14. ABSTRACT						
15. SUBJECT TERMS						
16. SECURITY CLASSIFIC	17. LIMITATION OF	18. NUMBER	19a. NAME OF			
a. REPORT unclassified	b. ABSTRACT unclassified	c. THIS PAGE unclassified	Same as Report (SAR)	OF PAGES 13	RESPONSIBLE PERSON	

Report Documentation Page

Form Approved OMB No. 0704-0188

Contents

- HYCOM subsurface heating parameterization
 - (1) Longwave radiation*
 - (2) Shortwave radiation
 - (3) Latent heat flux
 - (4) Sensible heat flux

Bulk Heat Flux Parameterization

- Total heat flux is available from archived products
 - o SST drifts if total flux alone is used to force an OGCM
- HYCOM uses model SST and a bulk heat flux parameterization
- Feedback between SST and heat flux to prevent SST drift
- No need for explicit relaxation to SST
- MICOM uses constant exchange coefficients
- HYCOM has
 - o several options for exchange coefficients
 - o a blackbody longwave correction

Subsurface Heating Parameterization

• Net heat flux at a given depth, z:

$$Q(z) = Q(0) + [Q_{SW}(0) - Q_{sw}(z)], \tag{1}$$

ullet Net heat flux absorbed at the sea surface, z=0:

$$Q(0) = Q_{LW} + Q_L + Q_S, \tag{2}$$

- o $Q_{\rm LW}$: net longwave radiation at the sea surface,
- o $Q_{\rm SW}$: net shortwave radiation at the sea surface,
- o Q_L : latent heat flux,
- o Q_S : sensible heat flux.

• NOTE:

- o HYCOM's "surface" heat flux is not Q(0), but
- o rather the near surface flux absorbed in layer 1
- o e.g., Q(1) when the top model layer is 1 m thick.


(1) Longwave Radiation

- Input from archived products (e.g., ECMWF, NCEP, etc)
- A correction is needed. Why?
 - o They use their model SST
 - o Different from HYCOM SST
- HYCOM uses a **blackbody correction** (Kara et al 2004a):

$$Q_{LW}(T_s) = Q_{LW}(T_{sa}) - (4.506 - 0.0554 T_s)(T_s - T_{sa}).$$

- o T_s : HYCOM SST
- o T_{sa} : Atmospheric model SST
- The effects of clouds are independent of SST

A linear approximation to the blackbody radiation



- Cubic formulation (Josey et al. 2003)
- Linear approximation (Kara et al. 2004a)

(2) Shortwave Radiation


- Previous parameterizations in HYCOM
 - o Jerlov water types (Halliwell 2004)
 - o 2-band scheme (Kara et al. 2004b)
 - o Turbidity-dependent split: red and blue spectrums.
 - o Based on SeaWiFS $k_{\rm PAR}$ climatology (2004c).
 - o Attenuation coefficient, k_{PAR} : depth-independent
- New parameterization in HYCOM (in progress)
 - o Fixed frequency ranges:
 - o visible spectrum (350–700 nm), also called PAR
 - o infrared spectrum (700–2400 nm)
 - o Will use absorption and backscattering coefficients
 - o k_{PAR} depends on **depth and solar angle**


The shortwave radiation at a given depth (z) is split into two parts:

$$Q_{\rm SW}(z) = Q_{\rm PAR}(z) + Q_{\rm IR}(z), \tag{3}$$

$$Q_{\text{PAR}}(z) = Q_{\text{PAR}}(0) \exp(-z \, k_{\text{PAR}}), \tag{4}$$

$$Q_{\rm IR}(z) = Q_{\rm IR}(0) \exp(-z k_{\rm IR}), \tag{5}$$







(3) Latent Heat Flux

- Bulk formulation: $Q_L = \rho_a C_L L V_a (q_a q_s)$
- Previous exchange coefficient (C_L) in HYCOM (Kara et al. 2002):
 - o based the COARE (v2.6) algorithm (Fairall et al. 1996)
 - o excluded $V_a < 4 \text{ m s}^{-1}, V_a > 20 \text{ m s}^{-1}$
 - o C_L was dependent on $(T_a T_s)$ and V_a
- New C_L parameterization in HYCOM (Kara et al. 2004d)
 - o based on the COARE (v3.0) algorithm (Fairall et al. 2003)
 - o includes V_a from 1 to 40 m s⁻¹
 - o C_L is dependent on (T_a-T_s) , V_a , and RH as well
- ullet NOTE: Calculate Q_L using HYCOM SST at each time step


Previous exchange coefficients for the latent heat flux (RH=100%)



New exchange coefficients for the latent heat flux (for varying RH) Is including relative humidity in C_L important?



What could be the typical error in latent heat flux without RH?



	Latent heat flux (W m ⁻²)				
	$V_a = 1 \text{ m s}^{-1}$	$V_a = 2 \text{ m s}^{-1}$	$V_a = 6 \text{ m s}^{-1}$		
100%	1.9	5.7	50.1		
80%	2.1	6.5	52.6		
60%	3.4	7.2	54.3		
40%	6.6	8.0	56.2		
20%	11.8	8.9	58.0		
00%	15.9	10.3	58.9		

 $Q_L = \rho_a \, C_L \, L \, V_a \, (q_a - q_s)$, where $T_a - T_s = 2^{\circ} \text{C}$, $q_a - q_s = 3 \, \text{g kg}^{-1}$

Summary

- Global HYCOM simulation with
 - o the RH-dependent exchange coefficients
 - o the depth-dependent shortwave radiation
- Shortwave radiation attenuation:
 - o need two satellite-based input fields for HYCOM
 - o (1) absorption coefficient
 - o (2) backscattering coefficient
 - o form a climatology (2001–2003) using MODIS

MODIS: Moderate Resolution Imaging Spectroradiometer